# Multi-turn design for cERL --- small footprint version ---

R. Hajima (羽島良一)

ERL Beam Dynamics Working Group Apr. 8, 2009

## Multi-turn ERL, Pros and Cons

## C Pros

- Save the cost for both construction and operation.
  - Linac  $\rightarrow$   $\frac{1}{2}$ , refrigerator  $\rightarrow$   $\frac{1}{2}$ , RF  $\rightarrow$   $\frac{1}{2}$ ...
- Smaller foot print

# 🙁 Cons

- Complicated beam optics
- Need more attention to BBU and CSR
- Larger HOM-load in the main linac

### Beam splitting & merging schemes



Fixed momentum ratio

$$P_2 / P_1 = const.$$

This type is considered here.



#### Variable momentum ratio

Design example was presented at the previous meetings.

### Beam splitter by round magnet



N.A. Vinokurov et al., RuPAC-2008.

## beam splitter for cERL



5

### isochronous arc with a reverse bend



### 2-loop design (small foot print version)



7

### 2-loop design (small foot print version)



### Previous design (larger footprint)

Inner loop  $\rightarrow$  similar to the CDR design, R<sub>56</sub>=0, FODO for the back straight Outer loop  $\rightarrow$  TBA arc,  $\rho$ =2m (ready for 400 MeV), R<sub>56</sub>=0, FODO for the back straight Linac  $\rightarrow$  9-cell (15 MeV) x 2 cavities x 2 modules



### Previous design (larger footprint)



#### Variable momentum ratio with a round magnet

Even if we fix  $\alpha_1$  and  $\alpha_2$ , the momentum ratio is variable by tuning "d".



### orbit correction for the variable momentum ratio



We fix the outer-loop orbit.

The momentum ratio is variable by moving the round magnet in x-direction. Shift in z-direction is also necessary to keep the outer-loop at the fixed position.

We need orbit correction for the inner loop.

![](_page_11_Figure_5.jpeg)

### possible scenario

- fabrication of all the magnets (max. ~240 MeV)
- installation of the outer loop and commissioning of a 60-MeV beam (9cell x 2 x 2) with the outer loop
- (a) SCA upgrade, and then 2-loop upgrade
  - energy upgrade (~120 MeV, 9-cell x 4 x 2) with the outer loop
  - installation of the inner loop and commissioning of a ~240-MeV beam with 2-loop ERL
- (b) 2-loop upgrade
  - installation of the inner loop and commissioning of a ~120-MeV beam